

**GENERAL NOTES:** 

REFER TO NEPTUNE METER INSTALLATION INSTRUCTION FOR ADDITIONAL GENERAL AND INSTALLATION REQUIREMENTS.

ALL WATER METER BE INSTALLED HORIZONTALLY. VERTICAL INSTALLMENT SHALL BE PROHIBITED.

BONDING OF ELECTRICAL SYSTEM TO THE WATER METER SHALL NOT BE ALLOWED.

SPRINKLER METERS ARE TO BE INSTALLED AFTER MAIN METER TO RECEIVE METERING CREDIT.

COMBINED WATER SERVICE 3" AND DOMESTIC SUPPLY 2" AND LARGER

STANDARD WM-010



COMMERCIAL METER DETAIL-B

CITY OF WEST CHICAGO
CONSTRUCTION SPECIFICATIONS,
STANDARDS, AND DETAILS